

**Addendum #1
May 23, 2022**

for

**HCC MISSOURI CITY CAMPUS
MEDICAL ASSISTANT
LAB RENOVATION**



Bids Due May 31, 2022

Addendum includes this cover + 1 (one) 8½x11 page



HCC MISSOURI CITY MEDICAL ASSISTANT LAB RENOVATIONS – ADDENDUM #1

Bids are due no later than May 31, 2022 by 2:00 pm.

Bids are due at the address shown here below:

Procurement Officer:
Arturo Lopez, Sr. Buyer

Houston Community College
3100 Main Street
Houston, TX 77002



The plans, specifications and addenda for the Missouri City lab renovation form part of the Contract Documents. This addendum modifies said documents as follows:

PART 1 - GENERAL

CLARIFICATIONS

RFI QUESTIONS AND ANSWER

Q1: What cable manufacture is in HCC specifications?

A1: Cabling to be done by HCC. Conduits and pulls is what is required from contractor as part of the scope of work.

Q2: Does the IDF room have existing connectivity ports?

A2: HCC will handle cabling to the IDF. This includes cable connectivity to the ports.

Q3: What color faceplates?

A3: Plates to match existing. White plastic data faceplate and stainless steel faceplate for electrical.

Q4: How many cable drops are needed? Drawing A.101 shows 4 dual drops and drawing E.101 shows 3 single drops at the Lectern and 2 dual drops by the door and in the ceiling (projector).

A4: Provide cable drops and electrical per sheet E.101. Note that sheet E.101 shows 3 existing drops at the Lectern and one existing at the ceiling. Existing drops to remain. The dual drop by the classroom door is to be provided per plans.

DRAWINGS

Item 1. A.101

A. Door elevation and schedule on sheet A.101 indicate hollow metal frame (HM-1). Change the door frame to clear anodized aluminum frame to match existing.

END OF ADDENDUM #1 DESCRIPTION

ADDENDUM 1